LOGO MINI INSTRUCTIONS SHEET PAGE: 1 of 6

TRIM & TRIMLESS MODELS : LOG3 - R / S - T / L - IC / CP /AT

IMPORTANT - READ CAREFULLY BEFORE INSTALLING FIXTURE. RETAIN THESE INSTRUCTIONS FOR FUTURE REFERENCE.

THIS PRODUCT MUST BE INSTALLED IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE AND ALL APPLICABLE LOCAL CODES, BY A PERSON FAMILIAR WITH THE CONSTRUCTION AND OPERATION OF THE PRODUCT, AND THE HAZARDS INVOLVED. PROPER GROUNDING IS REQUIRED FOR SAFETY.

# INSULATED CEILING / CHICAGO PLENUM INSTALLATION (IC / CP) INTEGRAL DRIVER (120V / 120-277V) DIMMING 0-10V (15%) - TRIAC / ELV (15%)


- A- REMOVE (4) PHILLIPS SCREWS IN ORDER TO OPEN HOUSING.
- B- FOR INSULATED CEILING (IC) INSTALLATION: INSTALL BX CABLE (NOT INCLUDED) USING BX CONNECTOR (INCLUDED).


  FOR CHICAGO PLENUM (CP) INSTALLATION: REMOVE KNOCKOUT, INSTALL AIR TIGHT CONDUIT AND CONDUIT CONNECTOR (NOT INCLUDED).


  \*0-10V DIMMING FOR INSULATED CEILING (IC): REMOVE EXTRA KNOCKOUT, INSTALL AIR TIGHT CONDUIT AND CONDUIT CONNECTOR (NOT INCLUDED).

  \*0-10V DIMMING FOR CHICAGO PLENUM (CP): REMOVE EXTRA KNOCKOUT, INSTALL AIR TIGHT CONDUIT AND CONDUIT CONNECTOR (NOT INCLUDED).
- C- MAKE ALL NECESSARY CONNECTIONS INSIDE THE BOX (SEE WIRING DIAGRAM) USING APPROPRIATE CONNECTORS (NOT INCLUDED).
- D- CLOSE THE HOUSING BY SCREWING THE (4) PHILLIPS SCREWS PREVIOUSLY REMOVED (A). LEAVE AT LEAST 6" (152mm) OF POWER CABLE ACCESSIBLE FROM UNDER THE CEILING.

A + B







INS-601

Last update: June 16, 2021

JP - R1


**LOGO MINI INSTRUCTIONS SHEET** PAGE: 2 of 6


TRIM & TRIMLESS MODELS : LOG3 - R / S - T / L - IC / CP /AT

E- ENGAGE THE (4) HANGER BARS THROUGH THE HOUSING MOUNTING SLOTS AVAILABLE AND CONNECT THEM TOGETHER.


F- FASTEN THE HANGER BARS TO THE CEILING BRACES WITH #8 SCREWS (NOT INCLUDED). THE HOUSING MUST BE FLUSH WITH THE BOTTOM OF THE CEILING BRACES.

G- INSTALL THE DRYWALL AND MAKE THE CUT-OUT OPENING (SEE DIMENSIONS BELOW).





G



Model	Housing	Cut-out dimensions (A)	Ceiling thickness	Clearance
LOG3R	BI-LOG3RT-IC/CP-XXX	Ø2 ¾" (Ø 71mm)	½" - 1" (3 - 27mm)	7½" (183mm)
	BI-LOG3RL-IC/CP-XXX	Ø 21/8" (Ø 73mm)		
LOG3S	BI-LOG3ST-IC/CP-XXX	25/8" x 25/8" (69 x 69mm)		
	BI-LOG3SL-IC/CP-XXX	2¾" x 2¾" (71 x 71mm)		


Last update: June 16, 2021


PAGE: 3 of 6


# AIRTIGHT HOUSING INSTALLATION (AT) INTEGRAL DRIVER (120V / 120-277V) DIMMING 0-10V (5%) - TRIAC / ELV (5%)

- A- REMOVE THE (4) PHILLIPS SCREWS IN ORDER TO OPEN THE HOUSING.
- B- REMOVE THE KNOCKOUT PLUG, INSTALL AN AIRTIGHT CONDUIT (NOT INCLUDED). AND A CONDUIT CONNECTOR (NOT INCLUDED).
  \*0-10V DIMMING: REMOVE AN EXTRA KNOCKOUT PLUG, INSTALL AN AIR TIGHT CONDUIT AND A CONDUIT CONNECTOR (NOT INCLUDED).
- C- MAKE ALL NECESSARY CONNECTIONS INSIDE THE BOX (SEE WIRING DIAGRAM) USING APPROPRIATE CONNECTORS (NOT INCLUDED).
- D- CLOSE THE HOUSING BY SCREWING THE (4) PHILLIPS SCREWS PREVIOUSLY REMOVED (A). LEAVE AT LEAST 6" (152mm) OF POWER CABLE ACCESSIBLE FROM UNDER THE CEILING.

#### A + B








S-601 Last update: June 16, 2021 JP - R




LOGO MINI INSTRUCTIONS SHEET PAGE: 4 of 6


TRIM & TRIMLESS MODELS : LOG3 - R / S - T / L - IC / CP /AT

- E- ENGAGE THE (4) HANGER BARS THROUGH THE HOUSING MOUNTING SLOTS AVAILABLE AND CONNECT THEM TOGETHER.
- F- FASTEN THE HANGER BARS TO THE CEILING BRACES WITH #8 SCREWS (NOT INCLUDED). THE HOUSING MUST BE FLUSH WITH THE BOTTOM OF THE CEILING BRACES.
- G- INSTALL THE DRYWALL AND MAKE THE CUT-OUT OPENING (SEE DIMENSIONS BELOW).
- H- INSURE AN AIRTIGHT SEAL AROUND THE CUT-OUT OPENING USING (2) SELF-DRILLING SCREWS (NOT INCLUDED) ANYWHERE AROUND THE CUT-OUT OPENING INSIDE THE NEOPRENE TAPE.










Model	Housing	Cut-out dimensions (A)	Ceiling thickness	Clearance
LOG3R	BI-LOG3RT-AT-XXX	Ø2 ¾" (Ø 71mm)	½" - 1½" (3 - 35mm)	7¼" (183mm)
	BI-LOG3RL-AT-XXX	Ø 21/8" (Ø 73mm)		
LOG3S	BI-LOG3ST-AT-XXX	25/8" x 25/8" (69 x 69mm)		
	BI-LOG3SL-AT-XXX	2¾" x 2¾" (71 x 71mm)		



**SISTEMALUX** 

Last update: June 16, 2021


JP - R

#### TRIM & TRIMLESS MODELS : LOG3 - R / S - T / L - IC / CP /AT

#### **BUTTERFLY MOUNTING ACCESSORY INSTALLATION**


A- REMOVE THE (2) PHILLIPS SCREWS (INCLUDED) ABOVE THE HOUSING'S MOUNTING BRACKETS.

B- SCREW THE BUTTERFLY BRACKET ACCESSORY (INCLUDED) USING THE (2) PHILLIPS SCREWS.




## HANGER BAR EXTENSION ACCESSORY INSTALLATION (BI-696-KIT)


A- ENGAGE THE (4) HANGER BAR EXTENSIONS THROUGH THE HOUSING MOUNTING SLOTS AND CONNECT THEM TOGETHER. B- SLIDE THE (4) HANGER BARS IN THE HANGER BAR EXTENSIONS AND ADJUST TO THE DESIRED LENGTH.




## TRIM KIT INSTALLATION (IC / CP / AT)

- A- ROUND MODEL: BEND AND HOLD THE SPRINGS AGAINST THE TRIM KIT AND ROTATE IN THE SPECIFIED DIRECTION (SEE BELOW) WHILE PUSHING UPWARD TO INSERT THE TRIM KIT INTO THE CEILING.
  - \*ONCE INSERTED, SECURE THE TRIM KIT TO THE CEILING BY SCREWING (2) #8 SCREWS (NOT INCLUDED).
- A- SQUARE MODEL: INSERT THE TRIM KIT INTO THE CEILING. TO HOLD THE KIT INSIDE THE HOUSING, SCREW THE (2) FIXATION BRACKET ADJUSTMENT SCREWS WITH A DRILL (RECOMMENDED). THE BRACKETS WILL OPEN AUTOMATICALLY WHILE SCREWING.
- B- FINISH THE ASSEMBLY BY PLASTERING, SANDING AND PAINTING.





В



S-601 Last update: June 16, 2021 JP -